

Contents

- 1 Offshore Wind Development 2011 1**
 - 1.1 Offshore Wind in Europe 1
 - 1.2 Offshore Wind in the U.S. 3
 - 1.2.1 Cape Wind: Massachusetts 6
 - 1.2.2 Coastal Point Energy-Galveston: Texas 7
 - 1.2.3 Bluewater Wind: Delaware 7
 - 1.2.4 Deepwater Wind: Rhode Island 8
 - 1.2.5 Garden State Offshore Energy: New Jersey 9
 - 1.3 Factors Impacting U.S. Development 9
 - 1.4 Atlantic Wind Connection 10
 - References 11
- 2 Offshore Wind Energy System Components. 13**
 - 2.1 Meteorological Systems. 13
 - 2.2 Support System 13
 - 2.2.1 Foundation. 15
 - 2.2.2 Transition Piece 22
 - 2.2.3 Scour Protection. 22
 - 2.3 Wind Turbine. 24
 - 2.4 Electricity Collection and Transmission. 26
 - 2.5 Offshore Substation 29
 - 2.6 Commissioning 30
 - References 30
- 3 Leasing and Stages of Offshore Development. 31**
 - 3.1 Project Location 31
 - 3.1.1 Baseline 31
 - 3.1.2 State Waters 31
 - 3.1.3 Outer Continental Shelf. 32

3.2	Development Process	33
3.2.1	Lease Acquisition	33
3.2.2	Assessment	33
3.2.3	Design	33
3.2.4	Construction	34
3.2.5	Commissioning	35
3.3	Texas Offshore Wind Lease Terms and Conditions	35
3.3.1	General Conditions	35
3.3.2	Galveston Island Lease Terms	37
3.4	Federal Legislation	39
3.5	Federal Offshore Wind Lease Terms and Conditions	40
3.5.1	Types of Access Rights	40
3.5.2	Auction Method	41
3.5.3	Leasing Process	42
3.5.4	Lease Terms	43
3.5.5	Development Process	44
3.5.6	Project Plans	44
3.5.7	Decommissioning	45
	References	45
4	Offshore Project Characteristics and Cost Factors	47
4.1	System Design	47
4.1.1	Design Requirements are Site-Specific and Multi-Dimensional	47
4.1.2	Configuration is Dictated by Prevailing Wind Directions and Aesthetic Appeal	48
4.1.3	System Capacities Reflect Commercial Status	48
4.1.4	Turbine Selection has Broad Impacts on System Design	50
4.1.5	Common Physical and Engineering Requirements	51
4.1.6	Installation Cost Comparisons are Facilitated by System Homogeneity	52
4.2	Markets	53
4.2.1	Tradeoffs in Vessel Selection and Availability	53
4.2.2	Installation Vessel Market Transparency is Poor	53
4.2.3	Varying Levels of Competition	54
4.2.4	Learning Curve Uncertainty	55
4.2.5	U.S. Project Economics and Financing Strategies	56
4.3	Contracts	56
4.3.1	Construction Contracts Define Cost Categories	56
4.3.2	Risk Allocation and Cost	58
4.3.3	U.S. Offshore Wind Will Likely Be Developed Using Multi-Contracting	58

4.4	Data Limitations.	60
4.4.1	Small Samples and Diverse Project Characteristics. . .	60
4.4.2	Small Samples Limit Analytic Techniques.	61
4.4.3	No U.S. Projects are Under Construction.	61
4.4.4	Apply Project Comparisons Cautiously	61
4.5	Cost	61
4.5.1	Vessel Dayrates are Market-Driven and Dynamic. . .	61
4.5.2	Impact of Catastrophic Failures	62
4.5.3	Port Facility and Location Impact Cost.	62
4.5.4	Weather Risk is Common in Offshore Construction	63
4.5.5	Public–Private Interface Impacts Cost Structure	63
4.6	Decommissioning	64
4.6.1	Decommissioning Timing is Defined by Regulatory Requirements	64
4.6.2	Decommissioning Projects are Unique but Share Common Features	64
4.6.3	Decommissioning Operations are Low-Tech and Routine	64
4.6.4	Learning Opportunities Will Occur.	65
4.7	Exposure and Liability	65
4.7.1	Joint and Several Liabilities.	65
4.7.2	Each Lease Represents a Different Level of Decommissioning Risk	65
4.7.3	Bonding Protects the Public Interest	66
4.7.4	Exposure Limits Vary With a Number of Factors. . .	66
4.7.5	U.S. Government is the Party of Last Resort	66
4.7.6	Bonding Cannot Provide Complete Protection from Noncompliance Risk.	66
4.7.7	Financial Failures in Offshore Wind May Be Less of a Threat.	67
4.7.8	All Bonding Procedures Have Limitations and Constraints	67
	References	67
5	Installation Strategies and Options	69
5.1	Foundation Installation	69
5.1.1	Monopiles	69
5.1.2	Jackets and Tripods	70
5.1.3	Factors Impacting Installation	71
5.1.4	Proposed U.S. Foundation Installation Methods	73
5.2	Turbine Installation.	73
5.2.1	Transport.	74
5.2.2	Installation.	74

5.2.3	Factors Impacting Installation	76
5.2.4	Proposed U.S. Turbine Installation Methods	78
5.3	Cable Installation	79
5.3.1	Inner-Array Cable.	80
5.3.2	Export Cable	81
5.3.3	Factors Impacting Installation	81
5.3.4	Proposed U.S. Cable Installation Methods	82
5.4	Substation Installation	82
5.5	European Installation Time Statistics	83
5.5.1	Data Source	83
5.5.2	Foundation.	83
5.5.3	Turbine	84
5.5.4	Cable	86
5.5.5	Substation	88
	References	88
6	Installation and Vessel Spread Requirements.	91
6.1	Vessel Categorization	91
6.1.1	Main Installation Vessels.	91
6.1.2	Cable-Laying Vessels	95
6.1.3	Vessel Spreads	95
6.2	Factors Impacting Vessel Selection.	98
6.2.1	Foundation.	99
6.2.2	Turbine	99
6.2.3	Cable	99
6.2.4	Substation	100
6.3	Support Spread.	101
6.3.1	Foundation Transport	101
6.3.2	Turbine Transport.	102
6.3.3	Cable	102
6.3.4	European Spread Requirements	102
6.3.5	Potential U.S. Spreads.	105
6.4	U.S. Vessel Procurement	106
6.4.1	Jones Act.	106
6.4.2	U.S. Fleet Circa 2011	108
6.4.3	Newbuilding and Modification	110
	References	111
7	Modeling Offshore Turbine Installation Vessel Dayrates in the U.S.	113
7.1	European Market Data	113
7.2	Dayrates as a Proportion of Newbuild Costs	113
7.3	Vessel Leasing	114

7.3.1	Component Approach	114
7.3.2	Net Present Value Approach	119
7.3.3	Limitations	119
7.4	Newbuild Program	120
7.5	Dayrate Estimation in the U.S.	121
7.5.1	Assumptions	121
7.5.2	Results	122
7.5.3	Limitations	123
7.6	Mobilization Costs	123
7.6.1	Tug Transport	124
7.6.2	Self-Propelled Transport	124
7.6.3	Heavy-Lift Vessel Transport	125
7.6.4	Example	125
7.7	Total Vessel Costs	127
	Appendix A. Leasing Dayrates	129
	Appendix B. Newbuilding Dayrate.	130
	References	132
8	Capital Cost Estimation: A Reference Class Approach	135
8.1	Comparative Versus Reference Approach	135
8.2	Source Data	136
8.2.1	Sample Set	136
8.2.2	Exclusion	136
8.2.3	Reference Class	136
8.2.4	Adjustment	136
8.2.5	Normalization	137
8.3	Capital Expenditures	137
8.3.1	Summary Statistics	137
8.3.2	Time Trends	141
8.3.3	Economies of Scale	142
8.3.4	Regression Model	143
8.4	U.S.-European Comparisons.	146
8.4.1	Turbines	146
8.4.2	Foundations	147
8.4.3	Cable	147
8.4.4	Installation.	148
8.4.5	Site Selection.	148
8.5	Cost Drivers.	150
8.5.1	Economic Recession	150
8.5.2	Commodity Prices	150
8.5.3	Supply Chain	151
8.6	Previous Estimates	151
8.7	Model Limitations	152

8.7.1	Sources of Error and Bias	152
8.7.2	Reference Class Constraints	153
	Appendix A. Cost Adjustment Example	154
	References	154
9	Modeling Offshore Wind Installation Costs	159
9.1	System Description	159
9.1.1	User Input	159
9.1.2	System Input	159
9.1.3	Derived Data	159
9.1.4	Model Output.	160
9.2	User Data	160
9.2.1	Project Characteristics	160
9.2.2	Vessel Selection	161
9.2.3	Installation Strategy	161
9.2.4	Adjustment Factor	162
9.3	System Data.	162
9.3.1	Vessel Specification	162
9.3.2	Expected Time	162
9.3.3	Vessel Dayrates	163
9.4	Installation Stage Computations	163
9.4.1	Foundation and Turbine Installation	163
9.4.2	Cable Installation	169
9.4.3	Substation Installation	170
9.4.4	Scour Protection	170
9.4.5	Mobilization	170
9.5	Model Parameterization.	171
9.5.1	Vessel Data	171
9.5.2	Foundations	171
9.5.3	Turbines	172
9.5.4	Cables	173
9.5.5	Substation	174
9.5.6	Scour Protection	174
9.5.7	Mobilization	175
9.6	Hypothetical Example	175
9.6.1	Set-Up.	175
9.6.2	Component Costs	175
9.6.3	Total Costs	176
9.6.4	Sensitivity Analysis	177
9.7	Proposed U.S. Projects	179
9.7.1	Cape Wind: Massachusetts	179
9.7.2	Bluewater Wind: Delaware	180
9.7.3	Coastal Point Energy-Galveston: Texas	182
9.8	Model Limitations	183

Appendix A. Parameter Verification	184
A.1 Temporal Parameters	184
A.2 Output Costs	185
References	186
10 Decommissioning Regulations and Workflows	189
10.1 Decommissioning Regulations	189
10.1.1 Regulatory Requirements	189
10.1.2 Decommissioning Bonds	190
10.1.3 Financial Instruments	190
10.2 Stages of Offshore Wind Decommissioning	191
10.2.1 Project Management and Engineering	191
10.2.2 Turbine Removal	191
10.2.3 Foundation and Transition Piece Removal	194
10.2.4 Met Tower and Substation Platform Removal	196
10.2.5 Cable Removal	196
10.2.6 Scour Protection	197
10.2.7 Site Clearance and Verification	197
10.2.8 Material Disposal	198
References	199
11 Structure Weight Algorithms	201
11.1 Weight Algorithms	201
11.1.1 Tubular Weight Algorithm	201
11.1.2 Foundations	201
11.1.3 Tower and Turbine	206
11.1.4 Cable	208
11.1.5 Substation	208
11.2 Example	209
References	210
12 Decommissioning Cost Estimation	213
12.1 Removal Options	213
12.1.1 Model Structure	213
12.1.2 Turbines	213
12.1.3 Foundations	214
12.1.4 Cable	214
12.1.5 Substation and Met Tower	214
12.2 Turbine Removal Model	215
12.2.1 Input	215
12.2.2 Self-Transport Model	215
12.2.3 Barge Model	216
12.2.4 Unconventional Model	217

12.2.5	Parameterization	218
12.2.6	Example	219
12.3	Foundation Removal	220
12.3.1	Input	220
12.3.2	Single-Vessel	220
12.3.3	OSV Support	221
12.3.4	Parameterization	222
12.3.5	Example	222
12.4	Cable	223
12.4.1	Input	223
12.4.2	Model	223
12.4.3	Parameterization	223
12.4.4	Example	224
12.5	Substation and Met Tower	224
12.6	Scour Protection	225
12.7	Site Clearance	226
12.7.1	Per-Turbine	226
12.7.2	Whole Farm	226
12.7.3	Example	227
12.8	Material Disposal Costs	227
12.8.1	Processing Costs	228
12.8.2	Scrap Value	229
12.8.3	Landfill Cost	229
12.8.4	Transport Costs	230
12.8.5	Reefing	230
12.8.6	Example	230
12.9	Cape Wind Decommissioning Scenarios	232
12.10	Decommissioning Costs at Proposed Offshore Wind Farms . . .	233
12.11	Discussion	234
	References	235